

AD-A099 061

ACKENHEIL AND ASSOCIATES INC PITTSBURGH PA
NATIONAL DAM INSPECTION REPORT. TREESDALE FARM DAM, BUTLER COUN--ETC(U)
MAR 81

F/G 13/13


DACW31-81-C-0027

NL

UNCLASSIFIED

1 of 1
AD99061

1 of 1



LEVEL

OHIO RIVER BASIN
BREAKNECK CREEK
BUTLER COUNTY


PENNSYLVANIA

NDI No. PA 01069
PENN DER No. 10-26

TREESDALE FARM DAM

TREESDALE FARM INC.

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



PREPARED FOR

DEPARTMENT OF THE ARMY
BALTIMORE DISTRICT, CORPS OF ENGINEERS
BALTIMORE, MARYLAND 21203

BY

ACKENHEIL & ASSOCIATES GEO SYSTEMS, INC.
CONSULTING ENGINEERS
1000 BANKSVILLE ROAD
PITTSBURGH, PENNSYLVANIA 15216

MARCH 1981

81 5

18 024

AD AUG 92 061

DTIC FILE COPY

Original contains color
plates: All DTIC reproductions
will be in black and
white.

DTIC
ELECTED
MAY 18 1981


DISTRIBUTION STATEMENT A
Approved for public release;
Distribution Unlimited

1

(6) OHIO RIVER BASIN
National Dam Inspection Report
TREESDALE FARM DAM
BUTLER COUNTY, COMMONWEALTH OF PENNSYLVANIA
(NDI NO. PA 01069
Penn DER NO. 10-26)
Ohio River Basin, Rock Creek
Butler County, Pennsylvania
TREESDALE FARM, INC.

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

NOV 1 1981



(12) 74

Prepared for: DEPARTMENT OF THE ARMY
Baltimore District, Corps of Engineers
Baltimore, Maryland 21203

Prepared by: ACKENHEIL & ASSOCIATES GEO SYSTEMS, INC.
Consulting Engineers
1000 Banksville Road
Pittsburgh, Pennsylvania 15216

CONTRACT DACW31-81-C-0027
(15)

Date: March 1981

DISTRIBUTION STATEMENT A
Approved for public release;
Distribution Unlimited

411785

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams for Phase I investigations. Copies of these guidelines may be obtained from the Department of the Army, Office of Chief of Engineers, Washington, DC 20314.

The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon visual observations and review of available data. Detailed investigations and analyses involving topographic mapping, subsurface investigations, materials testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify the need for such studies which should be performed by the owner.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of the dam depends on numerous and constantly changing internal and external factors which are evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some time in the future. Only through frequent inspections can some unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I investigations are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" (PMF) for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition, and the downstream damage potential

Accession For	
NTIS GRA&I	
DTIC TAB	
Unannounced	
Justification	
For	50 for
By	file
Distribution	
Available	
Dist	
A	

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

SYNOPSIS OF ASSESSMENT AND RECOMMENDATIONS

NAME OF DAM:	Treesdale Farm Dam
STATE LOCATION:	Pennsylvania
COUNTY LOCATION:	Butler
STREAM:	Unnamed tributary of Breakneck Creek, Ohio River Watershed.
DATE OF INSPECTION:	December 8, 1980
COORDINATES:	Lat. 40 40' 36" Long. 80 1' 42"

ASSESSMENT

Repairs and modifications to Treesdale Farm Dam were in progress at the time of the field reconnaissance. The downstream embankment slope was unvegetated and would be subject to erosion if the spillways were activated.

The dam is classified as a "small" size "significant" hazard dam in accordance with U.S. Army Corps of Engineers dam safety criteria. The 100 year frequency storm is considered an appropriate spillway design flood. For this design flood, analysis using the HEC-1 Dam Safety computer program indicates a maximum reservoir elevation of 1102.1 or 0.3 feet above the crest of the existing embankment. The spillway system of the existing dam is therefore considered temporarily inadequate. Modifications in progress call for the embankment crest to be increased to El. 1103.5. These modifications, once complete, will provide adequate spillway capacity.

Taking into account the unfinished modifications, the dam is considered to be in good condition. However, several conditions and procedures require attention and should be addressed as soon as possible. Recommendations for addressing these conditions and procedures are outlined below.

RECOMMENDATIONS

1. Temporary Measures


- a. Complete the repairs and modifications to the dam and develop a dense grass cover on the downstream slope of the embankment and auxiliary spillway.
- b. Remove the fill (temporary access road) obstructing the downstream channel.

2. Long-Term Measures (Require continual attention)

- a. Develop plans to provide positive upstream control of the reservoir drain pipe. Implement plans if pipe leakage becomes evident.
- b. Develop a formal flood surveillance and warning plan to advise downstream residents when high flows are expected. The plan should include an evacuation procedure.
- c. Inspect the downstream embankment slope for evidence of seepage and piping at least once each month. Implement corrective measures if piping is noted.

Treesdale Farm Dam

- d. Develop a more thorough maintenance program to regularly remove future tree growth from the embankment.



James D. Hainley

James D. Hainley, P.E.
Pennsylvania Registration No. 9453-E
Vice President

Paul A. D'Amato

Paul A. D'Amato, P.E.
Project Engineer


APPROVED BY:

James W. Peck
JAMES W. PECK
Colonel, Corps of Engineers
District Engineer

DATE: _____

5 May 81

TREESDALE FARM DAM



OVERVIEW OF DAM

TABLE OF CONTENTS

	<u>Page</u>
PREFACE	i
SYNOPSIS OF ASSESSMENT AND RECOMMENDATIONS,	ii
OVERVIEW PHOTOGRAPH	iv
 SECTION 1 - PROJECT INFORMATION	
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	3
 SECTION 2 - ENGINEERING DATA	
2.1 Design	6
2.2 Construction	8
2.3 Operation	9
2.4 Evaluation	9
 SECTION 3 - VISUAL INSPECTION	
3.1 Findings	10
3.2 Evaluation	12
 SECTION 4 - OPERATIONAL FEATURES	
4.1 Procedure	14
4.2 Maintenance of Dam	14
4.3 Inspection of Dam	14
4.4 Warning System	14
4.5 Evaluation	14
 SECTION 5 - HYDROLOGY AND HYDRAULICS	
5.1 Available Information	15
5.2 Evaluation	16
 SECTION 6 - STRUCTURAL STABILITY	
6.1 Available Information	17
6.2 Evaluation	17

TABLE OF CONTENTS (cont'd)

	<u>Page</u>
SECTION 7 - ASSESSMENT AND RECOMMENDATIONS . . .	
7.1 Assessment	19
7.2 Recommendations	19
APPENDIX A - VISUAL OBSERVATIONS CHECK LIST AND FIELD SKETCH	
Visual Observations Check List	A1
Field Sketch	A11
Field Profile and Section	A12
APPENDIX B - ENGINEERING DATA CHECK LIST	
APPENDIX C - PHOTOGRAPHS	
Photograph Key Map	C1
Photographs 1 through 4	C2
Photographs 5 through 8	C3
APPENDIX D - HYDROLOGIC AND HYDRAULIC ENGINEERING AND COMPUTER DATA	
Methodology	D1
Hydrologic and Hydraulic Engineering Data . . .	D3
HEC-1 Dam Safety Version	
Data Base	D4
HEC-1 Computer Analysis	D6
Rating Curve for Spillways	D10
Reservoir Storage Volume vs. Elevation	D13
Peak Inflow for 100 Year Storm	D14
Rainfall Distribution	D15
APPENDIX E - LOCATION PLAN AND PLATES	
Location Plan	E1
Plates 1 through 6A	E2
APPENDIX F - REGIONAL GEOLOGY	
Regional Geology	F1
Geologic Map	F2
Legend	F3

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM
TREESDALE FARM DAM
NATIONAL I.D. NO. PA 1069
Penn. DER No. 10-26

SECTION 1
PROJECT INFORMATION

1.1 GENERAL

- A. AUTHORITY: The Phase I investigation was performed pursuant to authority granted by Public Law 92-367 (National Dam Inspection Act) to the Secretary of the Army through the Corps of Engineers, to conduct inspections of dams throughout the United States.
- B. PURPOSE: The purpose of the investigation is to make a determination on whether or not the dam constitutes a hazard to human life or property.

1.2 DESCRIPTION OF PROJECT

A. DAM AND APPURTENANCES

1. Embankment: According to original design drawings, Treesdale Farm Dam was designed and constructed as an earthfill structure with a concrete core wall located at the dam centerline. The original embankment, constructed in 1925, is 320 feet long with a height of 19.8 feet from the downstream toe to the top of the core wall cap which serves as the dam crest. Compacted clay soil was used to construct upstream and downstream embankment sections.

Modifications to improve embankment stability, increase freeboard, and repair deteriorating concrete began in the summer of 1980 and are in progress at this time. The modifications are shown on Plates No. 7 to 9.

Design drawings do not indicate any type of drain system for the original embankment. Modifications now in progress include the installation of a drain system and the placement of additional fill on the downstream embankment slope.

2. Outlet Works: Outlet works consist of a reservoir drain and a pump system used for agricultural purposes. The reservoir drain reportedly consists of a 10 inch diameter cast iron pipe encased in concrete. The gate valve for this pipe is located near the downstream toe of the dam. A second gate valve located upstream from the core wall is not operable. The drain discharges into the principal spillway stilling basin.
3. Spillways: Design drawings for modifications now in progress indicate that three ungated spillways will be employed at Treesdale Farm Dam. These include:
- a. Principal Spillway: The principal spillway is located in the middle of the embankment and is used to control normal pool level and for flood discharge. The spillway consists

of a concrete weir (El. 1100.0) located at the core wall and a discharge channel with concrete bottom and sidewalls.

- b. Auxiliary Spillway: The auxiliary spillway is excavated in soil at the right abutment and is still under construction. Plans are to seed the channel in the Spring of 1981. The crest of the auxiliary spillway will be at El. 1100.5 or 0.5 feet above the weir crest of the principal spillway.
 - c. Emergency Spillway: The hydraulic design upon which the modifications now in progress have been based consider an 87 feet long section of the embankment between principal and auxiliary spillways to act as an emergency spillway. The existing embankment section is 140 feet in length. The top of the concrete core wall cap (El. 1101.5) for this section will function as a weir crest. Water will be discharged onto the downstream slope of the embankment, and gabions will be placed on both sides of the channel for erosion protection
4. Downstream Conditions: Treesdale Farm Dam is located across an unnamed tributary of Breakneck Creek which it intersects about 1.7 miles below the dam. Route 228 crosses the tributary about 1 mile below the dam. Between the dam and Rt. 228, the tributary is narrow and meanders through woodland. Further downstream, the tributary flows through the town of Mars and then intersects Breakneck Creek. Breakneck Creek is a tributary of the Beaver River which is part of the Ohio River watershed.
- B. LOCATION: The dam is located in Adams Township, Butler County about 1.3 miles southwest of Mars, Pennsylvania.
- C. SIZE CLASSIFICATION: Treesdale Farm Dam has a maximum storage volume (El. 1101.8) of 57 acre feet and a toe to crest height of 19.8 feet. The dam is classified as a "small" size structure according to Corps of Engineer guidelines.
- D. HAZARD CLASSIFICATION: Treesdale Farm Dam is classified as a "significant" hazard dam. If a dam failure would occur, four homes about 1 mile downstream of the dam could sustain damage though loss of life is not considered likely. Damage to Route 228 is also considered possible.
- E. OWNERSHIP: The dam is owned by Treesdale Farms, Inc. of Mars, Pennsylvania. All correspondence concerning the maintenance and operation of the dam should be directed to:
- Treesdale Farms, Inc.
RD #2
Mars, Pennsylvania 16046
Attn: Mr. Norman Datt
Phone No. (412) 625-1525
- F. PURPOSE OF DAM: The purpose of the dam is to provide a water supply reservoir for Treesdale Farms.
- G. DESIGN AND CONSTRUCTION HISTORY: Records indicate that construction of the dam began in 1924 and was completed in August, 1925. A construction permit, dated April 25, 1925, was issued by the Water

and Power Resource Board, Commonwealth of Pennsylvania after construction began. The name of the designer and contractor are unknown, though records indicate that Mr. A. H. Appel, an engineer contracted by Mr. J. C. Trees, owner of Treesdale Farms, was involved in the construction of the dam.

An inspection of Treesdale Farm Dam was made by Division of Dam Safety personnel (Department of Environmental Resources) during May, 1979. The reason for performing this inspection is unknown. Division of Dam Safety requested that the owner retain the services of a registered professional engineer to evaluate the stability and hydraulic capacity of the dam and recommend necessary modifications. This study was performed by Ronald E. Kelley Consulting Engineers, Greensburg, Pennsylvania during 1979 and 1980, and a report, dated March, 1980, was prepared. Records indicate that the recommended modifications and remedial measures proposed in the report were approved by the Division of Dam Safety on March 31, 1980. These modifications and remedial measures were not completed at the time of the field inspection (Dec. 8, 1980).

- H. NORMAL OPERATING PROCEDURE: Treesdale Farm Dam was designed to operate as an uncontrolled structure. Normal pool level is maintained at El. 1100.0 by the weir crest of the principal spillway. An ungated auxiliary spillway excavated into the right abutment and an 87 feet long embankment section designed to operate as an emergency spillway will also be employed to discharge flood flows once construction modifications are completed.

The reservoir drain is normally closed except when it is necessary to lower the water level for maintenance and repairs.

1.3 PERTINENT DATA

Note: The elevations given below are based on mean sea level and were obtained from the original design plans dated 1925 (Plates No. 1 to 5). The elevation shown on drawing prepared by Ronald E. Kelley Consulting Engineers were based on an assumed elevation of 1105.5 feet for the principal spillway crest. The elevations on these drawings are 5.5 feet greater than elevations based on mean sea level.

- A. Drainage Area: 0.49 sq. mi.
- B. Discharge at Dam Facility:
- | | |
|--|----------|
| Maximum flood at dam facility | Unknown |
| Spillway capacity at top of existing embankment @ El. 1101.8 (with emergency spillway activated) | 211 cfs |
| Spillway capacity at top of proposed embankment @ El. 1103.5 (with emergency spillway activated) | 1335 cfs |
- C. Elevations:
- | | |
|----------------------------|--------|
| Top of existing embankment | 1101.8 |
| Top of proposed embankment | 1103.5 |

Normal pool	1100.0
Principal (ungated) spillway overflow crest	1100.0
Crest of auxiliary spillway Existing elevation	1100.1
Proposed elevation	1100.5
Crest of emergency spillway	1101.5
Maximum tailwater	Unknown
Inlet invert of pond drain	Approx. 1083
Outlet invert of pond drain	Approx. 1082
Lowest point at toe of embankment	1082
 <u>D. Reservoir Length</u>	
Length of normal pool	1000 feet
Length of maximum pool Existing (El. 1101.8)	1030 feet
Proposed (El. 1103.5)	1050 feet
 <u>E. Reservoir Storage</u>	
Top of existing embankment	57 acre-feet
Top of proposed embankment	70 acre-feet
Top of core wall (El. 1101.5)	55 acre-feet
Principal (ungated) spillway overflow weir crest (El. 1100.0)	45 acre-feet
Normal pool	45 acre-feet
Sediment pool	Unknown
 <u>F. Reservoir Surface</u>	
Top of existing embankment	7.0 acres
Top of proposed embankment	8.0 acres
Top of core wall (El. 1101.5)	6.8 acres
Principal (ungated) spillway overflow weir crest	5.9 acres
Normal pool	5.9 acres
Sediment pool	Unknown
 <u>G. Embankment</u>	
Type	Earthfill
Length	320 feet
Height	
Existing	19.8 feet
Proposed	21.5 feet
Existing crest width	3 - 22 feet
Proposed crest width	10 - 35 feet
Slopes	
Downstream	3.5H:1V
Upstream	2.0H:1V
Impervious core	Yes
Cutoff provisions	Concrete core wall founded on rock
Grout curtain	None reported

H. Regulating Outlet (Principal Spillway)

Type	Overflow spillway with concrete weir
Length of weir	15.7 feet
Weir crest elevation	1100.0

I. Auxiliary Spillway

Type	Trapezoidal channel excavated in soil
Width	
Existing	14 feet
Proposed	20 feet
Crest elevation	
Existing	1100.1
Proposed	1100.5
Gate	None
Downstream Channel	Soil (to be seeded in Spring, 1981)
Upstream Channel	Soil (to be seeded in Spring, 1981)
Length of Channels	60 feet

J. Emergency Spillway

Type	Overflow spillway with concrete weir (core wall)
Width	
Existing	140 feet
Proposed	87 feet
Crest elevation	1101.5
Gate	None
Downstream Channel	Downstream slope of embankment
Upstream Channel	None
Length of Channel	Discharges on downstream slope of embankment

K. Outlet Works (Reservoir Drain)

Type	10 inch diameter C.I. pipe encased in concrete
Inlet	Type unknown
Conduit length	Approximately 140 feet
Gate Valve	Yes, at downstream toe
Anti-Seep collars	None reported. (except core wall)

SECTION 2
ENGINEERING DATA

2.1 DESIGN

- A. Data Available: The following reports, drawings, and records may be obtained from the Pennsylvania Department of Environmental Resources, Harrisburg, Pennsylvania:
1. Miscellaneous design drawings of original embankment dated March 30, 1925.
 2. Specifications for constructing the original embankment dated April 9, 1925.
 3. Permit application to construct dam dated April 9, 1925.
 4. Miscellaneous correspondence between Water and Power Resources Board and J.C. Trees (owner) concerning construction of dam.
 5. Dam construction permit from Water and Power Resources Board dated April 13, 1925.
 6. Inspection report, dated October 21, 1926, prepared by Water and Power Resource Board.
 7. Correspondence concerning permit to draw down reservoir, dated August, 1955.
 8. Inspection report dated August 7, 1967 prepared by Division of Dams and Encroachment (DER).
 9. Correspondence concerning an April 20, 1979 inspection made by the Division of Dam Safety (DER).
 10. Report entitled "Reinforcement of Embankment, Concrete Core Wall and Spillway for Earth Dam at Apple Orchard of Treesdale Farms, Inc." prepared by Ronald E. Kelley Consulting Engineers, Greensburg, Pennsylvania and dated March, 1980.
 11. Correspondence dated March 31, 1980 from the Division of Dam Safety (DER) stating approval of proposed modifications.
- B. Design Features: The design criteria used to construct the original embankment in 1925 is unknown. Plans and specifications for this construction were approved by the Water and Power Resource Board, Commonwealth of Pennsylvania. Design modifications now in progress were approved by the Division of Dam Safety, (Department of Environmental Resources). Principal design features are illustrated on Plates No. 1 through 9.
1. Field Investigation: There are no records indicating that a field investigation was undertaken prior to the construction of the original embankment. A survey of the original embankment was performed by Ronald E. Kelley Consulting Engineers in 1979 for the purposes of their study.

2. Embankment: Design drawings indicate that the embankment was designed as an earthfill structure with a core wall made of reinforced concrete. Clay soil, placed in 6 inch thick layers and compacted, was used to construct upstream and downstream embankment sections. Records indicate that the core wall was founded on shale for its entire length as shown on the design drawings.

The upstream and downstream sections of the original embankment were not constructed as shown on the plans (Plate No. 1). Fill was not placed to the top of the core wall as shown. An inspection report, dated July 3, 1926, stated, "The earth embankment on the downstream side varies from about 3 feet below the top at the left end to 5 feet at the left of the spillway, on the upstream side, the embankment is about 3.5 feet below the top."

The inclinations of the upstream and downstream slopes of the original embankment are 2H:1V and 2.5H:1V respectively. Modifications now in progress include the placement of additional fill on the downstream slope (Plate No. 7 and 8) and installation of a drain system (Plate No. 9). The inclination of the modified downstream slope section left of the principal spillway is 3.5H:1V rather than the 2H:1V slope shown on the modification plans (Plate No. 8). The drain system was installed to intercept seepage from the original embankment as shown on Plate No. 9. Recent repair work also includes the replacement of the core wall cap and grouting a crack in the core wall.

3. Outlet Works: The dam was designed with a 140 feet long reservoir drain pipe placed through the embankment. The pipe is 10 inches in diameter, made of cast iron, and encased in concrete. The original design drawings (Plate No. 1) show two gate valves on this pipe; one located upstream of the core wall and the other at the downstream toe of the embankment. The valve at the core wall is not operable and it is only necessary to open the downstream valve to operate the reservoir drain. A PVC pipe extension has been connected to this gate valve and discharges into the downstream channel.

A pump system is also in use at the dam facility to supply water for agricultural purposes. The pump house for this system is located adjacent to the core wall about 70 feet right of the principal spillway.

4. Spillways: Three ungated spillways will be used for flood discharge. These are described below:

- a. Principal Spillway: The principal spillway, consisting of a concrete weir and discharge channel, is located at the middle of the embankment. This spillway is used to maintain normal pool level at El. 1100.0 and for flood discharge. The spillway weir is 15.7 feet in length and is at a level 1.5 feet below the top of the core wall. Modifications are planned to increase the hydraulic capacity of this spillway. Modifications include increasing the embankment height by placing additional fill on the downstream slope and constructing a trapezoidal shaped principal spillway channel lined with riprap (Plate No. 8).

- b. Auxiliary Spillway: The auxiliary spillway is in the process of being excavated into soil at the right abutment. During our December 8, 1980 field reconnaissance, the spillway channel was about 14 feet wide with a crest elevation 1100.1 feet or 0.1 feet above normal pool level. Records indicate that an auxiliary spillway was constructed at the right abutment when the dam was built in 1925. It is unknown what has happened to the concrete apron of the original auxiliary spillway or why the area was filled in. Modifications now in progress call for grading the channel to El. 1100.5 and seeding during Spring, 1981.
- c. Emergency Spillway: A 87 feet section of the embankment between the principal and auxiliary spillway will be used for an emergency spillway. As shown on Plate No. 2, the embankment has a height of about 7 feet at the proposed emergency spillway location. This section of embankment will be overtopped when the reservoir level exceeds the height of the core wall (El. 1101.5) which will function as a spillway crest. Modifications call for the downstream slope to be seeded and for rock gabions to be used at the sides of this section for erosion protection.

2.2 CONSTRUCTION

- A. CONTRACTOR: The contractor responsible for the construction of the dam in 1925 is unknown. Modifications currently in progress are being made by W. M. Aiken and Sons, Mars, Pennsylvania.
- B. CONSTRUCTION PERIOD: Construction of the dam began in 1924 and was completed in August, 1925. Modifications were begun during the summer of 1980. The owner claims that the modifications will be completed during Spring, 1981.
- C. FIELD CHANGES:
 - 1. Original Construction: Features which differ from the original design drawings dated March 1925 are described below:
 - a. Fill for the upstream and downstream embankment sections was placed 3 to 5 feet below the top of the core wall rather than to the top of the wall.
 - b. Fill was placed in the auxiliary spillway area and the concrete apron was removed.
 - 2. Current Modifications: Features which differ from the design drawings included in the report prepared by Ronald E. Kelley Consulting Engineers are described below. Other changes may be evident after the design modifications are complete.
 - a. Fill placed on the downstream embankment slope has an inclination of 3.5H:1V rather than 2.0H:1V.
 - b. PVC pipe was used for the reservoir drain extension rather than cast iron pipe and the drain discharges directly into the stilling basin instead of into an adjoining channel as shown on Plate No. 7.

D. CONSTRUCTION INSPECTION: A site inspection was made by representatives of the Water and Power Resources Board, Commonwealth of Pennsylvania on October 21, 1926. The inspection report states that "this dam has been built according to the plans approved." It was noted, however, that embankment fill was not placed to the top of the core wall.

2.3 OPERATION. The owner, Treesdale Farms Inc. of Mars Pennsylvania is responsible for the operation of the dam. Flood discharge is uncontrolled and operation records are not maintained. The reservoir drain is normally closed except when it is necessary to lower the reservoir for repairs to the dam or for removal of sediment.

2.4 EVALUATION.

- A. AVAILABILITY: Available design information and drawings were obtained from the Pennsylvania Department of Environmental Resources.
- B. ADEQUACY: The available design information is considered adequate for the purposes of this Phase I inspection report.
- C. VALIDITY: Based on the available data, there appears to be no reason to question the validity of the design information used for this report.

SECTION 3 VISUAL INSPECTION

3.1 FINDINGS

A. GENERAL: The on-site reconnaissance of Treesdale Farm Dam was performed on December 8, 1980 and consisted of:

1. Visual observations of the earth embankment, abutments, principal spillway, and auxiliary spillway channel.
2. Visual observations of exposed sections of the core wall.
3. Evaluation of the downstream hazard potential.
4. Visual observation of the reservoir shoreline, upstream dams, and downstream channel.
5. Transit stadia survey of relative elevations along the top of the core wall, embankment crest, and across the downstream slope.

The visual observations were made during a period when the reservoir was about 2 feet lower than normal pool level. The reservoir was drawn down so that repairs and modifications to the dam could be performed.

A visual description checklist and field sketch are given in Appendix A. Specific observations are shown on photographs in Appendix C.

B. EMBANKMENT:

1. Surficial: Embankment modifications were in progress at the time the field reconnaissance was made. Fill, consisting of predominately clay soil, had been placed on the downstream slope in order to increase the crest elevation along a section of embankment and to improve embankment stability. Due to construction not being completed, the downstream slope was unvegetated. Mr. Norman Datt of Treesdale Farms has stated that these areas will be seeded during Spring, 1981. The upstream slope was submerged and hence could not be observed. The concrete cap of the core wall was recently reconstructed and the exposed portion of the core wall appeared in excellent condition. The crest of the fill on the downstream slope left of the principal spillway varies from El. 1101.8 to El. 1102.5 rather than El. 1103.5 as proposed.
2. Seepage: No noticeable seepage was observed emanating from the downstream embankment slope. Water was present in the downstream channel even though the principal spillway was not in operation due to reservoir drawdown. Modifications now in progress include the installation of a drain system to intercept seepage from the original embankment (Plate No. 9). No discharge from the outlet pipes for this drain was noted during the site reconnaissance. It is unknown if the water in the downstream channel is caused by discharge from the drain system or from springs emanating from the abutments.

3. Wet Zones: A wet zone with ponded water was observed below the downstream toe and to the left of the downstream channel. The wet zone is situated in a low lying area and is believed subject to surface runoff from rainfall and springs in the left abutment. A spring emanating from the left abutment was observed and is shown on the field sketch.

C. DOWNSTREAM CONDITIONS:

1. Channel: The channel directly below the dam has been straightened and cleared of debris. The bottom and side slopes of the channel are unvegetated and final grading has not been completed. About 100 feet below the dam, the channel is obstructed by fill placed over a 12 inch diameter pipe (Photo No. 6). This was constructed for access to the left abutment and it will reportedly be removed when construction operations are complete. Downstream from this obstruction, the channel is narrow and meanders through woodland for about 1 mile before intersecting Route 228.
2. Development: Treesdale Farm Dam is located on an unnamed tributary of Breakneck Creek, which it intersects about 1.7 miles downstream of the dam. Route 228 crosses the tributary about 1 mile downstream of the dam. At this location, there are 4 houses adjacent to and within a 10 feet elevation difference of the tributary. The tributary then flows through the town of Mars before intersecting with Breakneck Creek. Between Route 228 and Breakneck Creek, there are about 10 buildings located adjacent to and within a 10 feet elevation difference of the tributary.

D. APPURTENANT STRUCTURES:

1. Reservoir Drain: The 10 inch diameter reservoir drain was reported to be operational at the time of the site reconnaissance. Access to the gate valve is by a manhole located near the downstream toe of the dam. The gate valve was recently opened to lower the reservoir for dam repairs and hence was not exercised.
2. Principal Spillway: Due to the lowered reservoir level, the principal spillway was not discharging at the time of the site reconnaissance. The concrete weir and spillway channel appeared in excellent condition. As part of the repair work in progress, the weir and sidewalls of the channel have been reconstructed and the channel bottom was sandblasted and coated with a bituminous mastic (Photo No. 4). Riprap along the sides of the spillway and in the stilling basin had yet to be placed. In its existing condition, the spillway will discharge onto unvegetated soil at the toe of the embankment.
3. Auxiliary Spillway: The auxiliary spillway was partially excavated into the left abutment at the time of the site reconnaissance. It is being excavated into soil and the channel, due to construction, was unvegetated. No evidence of the concrete apron of the original auxiliary spillway, constructed in 1925, was observed.

4. Emergency Spillway: Construction modifications to enable an 87 feet long section of the embankment between principal and auxiliary spillways to function as an emergency spillway were not completed at the time of the site reconnaissance. Over-topping of this section of the existing embankment will result in water being discharged onto a 140 feet long section of unvegetated embankment slope.

- E. INSTRUMENTATION: No instrumentation was observed during the inspection.
- F. RESERVOIR: The slopes of the reservoir shoreline have a moderate inclination and are vegetated with trees and brush. No evidence of instability was noted. Three small dams are located upstream of the reservoir as shown on Plate No. 6. These structures were constructed as sedimentation ponds and the dam for Pond #1 has been breached. Evidence of excessive sedimentation in the main reservoir was not evident.

3.2 EVALUATION

- A. GENERAL: As previously stated, construction modifications were in progress at the time of the site reconnaissance. A comparison between all features of the existing embankment and the design drawings was therefore not possible. Deviations from design, to the extent now discernible, along with a description of potentially hazardous conditions (mostly temporary conditions caused by construction operations) are detailed below.
- B. EMBANKMENT: The downstream slope of the embankment is unvegetated and would be prone to erosion in the event the dam is overtopped. Although temporary, this condition is considered to be a serious deficiency.

The crest of the fill on the downstream slope left of the principal spillway varies from El. 1101.8 to El. 1102.5 rather than El. 1103.5 as proposed (Plate No. 8). Until construction is completed, the dam will have less freeboard than planned. This may or may not be a deficiency, depending upon the results of the hydrologic/hydraulic analysis.

C. APPURTENENT STRUCTURES:

1. Reservoir Drain: The water in the cast iron reservoir drain pipe is under pressure due to the gate valve being located near the downstream toe of the embankment. Leakage from this pipe could result in internal erosion of the downstream slope and possible instability.
2. Principal Spillway: In its existing condition, the spillway, if activated, will discharge onto unvegetated soil at the downstream toe of the embankment. Until the riprap stilling basin is constructed, this condition could cause erosion of the downstream toe area and result in possible instability.
3. Auxiliary Spillway: The auxiliary spillway channel has been partially excavated into soil at the left abutment and is unvegetated. Until suitable erosion protection is provided, discharge from the channel would cause erosion and possible instability of the embankment.

4. Emergency Spillway: When overtopped, an embankment section between the principal and auxiliary spillways would function as an emergency spillway. Erosion of the unvegetated downstream slope would occur and embankment instability is considered possible.

SECTION 4 OPERATIONAL FEATURES

- 4.1 PROCEDURE. Normal pool level is maintained by the uncontrolled weir crest of the principal spillway. Normal operating procedure does not require a dam tender. The only operational features of the dam are the reservoir drain gate valve which is normally kept closed and the pump system for water supply which is used as needed.
- 4.2 MAINTENANCE OF DAM. The dam is maintained by the owner; Treesdale Farms Inc., Mars, Pennsylvania. Maintenance normally consists of removing debris and cutting brush. Maintenance is generally performed on an "as-needed" basis. Major renovations were in progress at the time of the site reconnaissance.
- 4.3 INSPECTION OF DAM. Inspections are performed by personnel of Treesdale Farms on approximately a weekly basis. The inspections generally consist of visually examining the embankment and spillway channel for debris and erosion. Records indicate that the dam was inspected by state personnel in 1926, 1967, and 1979.
- 4.4 WARNING SYSTEM. There is no warning system or formal emergency procedure to alert downstream inhabitants upon the threat of a dam failure.
- 4.5 EVALUATION. Based on the observations made during the site reconnaissance, conversation with Treesdale Farm personnel, and photographs of the dam prior to the start of renovations, the maintenance and inspection procedures being followed at Treesdale Farm Dam are considered adequate with the exception of the following:
 - A. Photographs of the dam prior to the start of renovations showed several large trees growing on the embankment. Future tree growth on the embankment should be removed on a routine basis.
 - B. Records indicate that seepage from the original embankment was present in the past. A Division of Dam Safety inspection report, dated May 21, 1979, states that "the embankment was found to have problems on the right side. In this area there is seepage with piping evident." Although the concrete core wall has been repaired and a drain system has been constructed, the downstream slope of the existing embankment should be routinely inspected for evidence of seepage and piping.

SECTION 5
HYDROLOGY AND HYDRAULICS

5.1 AVAILABLE INFORMATION

- A. DESIGN DATA: Treesdale Farm Dam has a watershed area of 312 acres which is primarily woodland and orchard. The watershed area has a maximum elevation of 1300 feet above mean sea level (MSL). The dam impounds a reservoir with a surface area of 5.9 acres and storage volume of 45 acre-feet at normal pool level (El. 1100.0). At the existing crest elevation of 1101.8, the dam can impound 57 acre-feet. If the crest height is increased to El. 1103.5 as shown on the design drawings, the dam can impound 70 acre-feet.
- B. EXPERIENCE DATA: Records of reservoir levels are not kept though Treesdale Farms does maintain records of rainfall. There is no record or report of the embankment ever being overtopped during a period of heavy rainfall.
- C. VISUAL OBSERVATIONS: The planned modifications to the principal, auxiliary, and emergency spillways were not completed at the time of the field reconnaissance. Observed conditions that would affect the performance of these spillways until the modifications are completed are summarized below:
1. Riprap on the sides of the principal spillway and in the stilling basin was not in place.
 2. The excavation for the auxiliary spillway was not completed and the channel was not vegetated.
 3. Fill operations on the downstream embankment slope were not completed. The slope was not vegetated and gabions for erosion protection were not in place.
- D. OVERTOPPING POTENTIAL: The Corps of Engineer guidelines recommend a spillway design flood (SDF) of 100 year frequency to 0.5 times Probable Maximum Flood (PMF) for "small" size, "significant" hazard dams. Based on the size of the reservoir (57 acre-feet) and the distance to the closest damage center (1 mile), the 100 year frequency storm was considered an appropriate spillway design flood.

According to the U.S. Weather Bureau Technical Paper No. 40, the 100 year frequency rainfall amount for the dam site is 5.0 inches/ 24 hour. The report prepared by Ronald E. Kelley Consulting Engineers for the proposed modifications did include flood routing calculations using a rectangular hydrograph having an intensity of 5 inches/1 hour. For this rainfall amount, these calculations indicate a maximum reservoir elevation of 1102.7 feet and a peak inflow rate of 540 cfs using the Rational Method.

In order to evaluate if runoff from the 100 year frequency storm would overtop the existing embankment, an analysis was performed using the "HEC-1 Dam Safety Version" computer program and multiple regression flow frequency equation for the Ohio River Basin supplied

by the Baltimore District Corps of Engineers. A peak inflow rate of 497 cfs was calculated using the regression equation for the 100 year frequency storm. A summary of the dam safety analysis and supporting calculations are included in Appendix D.

5.2 EVALUATION

In order for the peak inflow of the computer developed hydrograph to closely approximate the 497 cfs required, it was necessary to increase the 100 year frequency rainfall by a factor of 2.4. The analysis indicated a maximum reservoir elevation of 1102.1 feet or a level 0.3 feet above the crest of the existing embankment. The spillway system of the existing dam is therefore considered temporarily inadequate.

Modifications in progress call for the embankment crest to be increased to El. 1103.5. Completion of proposed modifications will provide a spillway capacity of about 1600 cfs. The dam will therefore have adequate spillway capacity once the proposed modifications are completed.

SECTION 6 STRUCTURAL STABILITY

6.1 AVAILABLE INFORMATION

a. DESIGN AND CONSTRUCTION DATA:

1. Subsurface Exploration: The available information did not make any reference to a subsurface exploration of the dam site. The core wall is reportedly founded on shale bedrock and embankment soils obtained on site are predominately clay.
2. Laboratory Testing: No reference to laboratory testing was found from available sources.
3. Slope Stability Analysis: No calculations or references were found from available information.

b. OPERATING RECORDS: Operating records are not maintained for Treesdale Farm Dam.

c. POST CONSTRUCTION CHANGES: Modifications to improve embankment stability were in progress at the time of the site reconnaissance. Embankment modifications include the placement of additional fill on the downstream slope and the installation of a drain system to intercept seepage. These modifications are described in Section 2.1 B and 2.2 C.

6.2 EVALUATION

a. DESIGN DOCUMENTS: The available design documentation did not include an evaluation of structural stability.

b. VISUAL OBSERVATIONS: No evidence of instability was noted for the existing structure although structural modifications were in progress at the time of the site reconnaissance. Additional fill was to be placed on the downstream embankment slope and the slope was unvegetated. These conditions aside, the structural condition of the embankment is considered good. However, the potential for an unstable condition exists because of the following:

1. Water in the reservoir drain pipe is under pressure due to the gate valve being located near the downstream toe of the embankment. Leakage from this pipe could result in internal erosion of the downstream slope and possible instability.
2. Until dense vegetation is established on the downstream embankment slope and erosion control provisions are completed, the slope will be subject to erosion and possible instability if the spillways were to be activated.

- c. Performance: The original embankment was reportedly never overtopped and has been structurally stable since its construction in 1925. The modifications now in progress are expected to improve the stability of the embankment. Cracks in the core wall have been sealed and an extensive drain system has been installed to intercept seepage. Additional fill placed on the downstream embankment slope should also improve stability by reducing the slope inclination from 2.5:1V to 3.5H:1V.
- d. Seismic Stability: The dam is located in a Seismic Zone 1 area (low seismic probability). Based upon this low seismic probability and recommended criteria for the evaluation of seismic stability of dams, the seismic stability of the embankment is presumed to be adequate under these earthquake conditions.

SECTION 7
ASSESSMENT AND RECOMMENDATIONS

7.1 ASSESSMENT

- A. EVALUATION: Repairs and modifications to the embankment and appurtenant structures were in progress at the time of the site reconnaissance. Taking into account the unfinished modifications, the dam is considered to be in good condition.

The downstream embankment slope and auxiliary spillway channel were unvegetated and rock gabions and riprap for erosion protection were not in place at the time of the site inspection. Until modifications are complete, the embankment will be subject to erosion if the spillways are activated.

The "small" size and "significant" hazard classification of the dam dictates a Spillway Design Flood of 100 year frequency to 1/2 PMF. The 100 year frequency storm was selected as the Spillway Design Flood. For this design flood, the crest of the existing embankment (El. 1101.8) will be overtopped by 0.3 feet. The spillway system of the existing dam is therefore considered temporarily inadequate. Proposed modifications now in progress will provide adequate spillway capacity once completed.

- B. ADEQUACY OF INFORMATION: The construction drawings and reports available for this review were of sufficient detail to adequately conduct a Phase I study.
- C. URGENCY: The recommendations presented in Section 7.2 should be implemented as soon as possible.
- D. NECESSITY FOR ADDITIONAL STUDY: At the present time, there is no need for additional study.

7.2 RECOMMENDATIONS

A. TEMPORARY MEASURES

1. Complete the repairs and modifications to the dam and develop a dense grass cover on the downstream slope of the embankment and auxiliary spillway.
2. Remove the fill (temporary access road) obstructing the downstream channel.

B. LONG-TERM MEASURES (REQUIRE CONTINUAL ATTENTION)

1. Develop plans to provide positive upstream control of the reservoir drain pipe. Implement plans if pipe leakage becomes evident.
2. Develop a formal flood surveillance and warning plan to advise downstream residents when high flows are expected. The plan should include an evacuation procedure.
3. Inspect the downstream embankment slope for evidence of seepage and piping at least once each month. Implement corrective measures if piping is noted.

4. Develop a more thorough maintenance program to regularly remove future tree growth from the embankment.

APPENDIX A

VISUAL OBSERVATIONS CHECK LIST AND FIELD SKETCH

VISUAL OBSERVATION CHECK LIST

Name Dam Treesdale Farm Dam County Butler State Pennsylvania National ID # 1069

Type of Dam Earth with Concrete Core Wall Hazard Category Significant

Date(s) Inspection Dec. 8, 1980 Weather Cloudy Temperature 550 F

Inspection Review Date Dec. 19, 1980

Pool Elevation at Time of Inspection 1098 ft. *(2 ft. below normal pool - See note #1) Tailwater at Time of Inspection See Note #2 M.S.L.

Inspection Personnel:

James D. Hainley, P.E. Ackenheil & Associates
 Timothy E. Debes, P.E. Ackenheil & Associates
 Paul A. D'Amato, P.E. Ackenheil & Associates
 Norman Datt, Vice-President Treesdale Farms, Inc.

Supervising Principal
 Hydrologist & Project Manager
 Geotechnical Engineer

Recorder Paul A. D'Amato

*Based on spillway crest elevation of 1100 feet obtained from design plans.

Notes

1. Reservoir level was lowered to allow for structural modifications.
2. No spillway discharge. Downstream channel blocked by temporary access road.

A-1

AABM Project No. B80074
 Penn DER I.D. No. 10-26

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS*
SURFACE CRACKS	None observed.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	None. Additional fill being placed as part of structural modification.	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Good. Concrete cap of core wall was replaced during November, 1980. Additional fill being placed on downstream slope as part of structural modification.	
RIPRAP FAILURES	None	

EMBANKMENT

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
SETTLEMENT		Could not evaluate evidence of any settlement because additional fill was recently placed on downstream slope.
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM		Auxiliary spillway at right abutment was partially excavated. Areas at embankment and abutment junction are not vegetated.
ANY NOTICEABLE SEEPAGE		No seepage was observed. Wet zone located below downstream toe and to the left of downstream channel. Water also observed in downstream channel (no spillway discharge).
STAFF GAGE AND RECORDER		Rainwater gauge at farm office.
DRAINS		No drain system installed in original dam. Drain system to intercept seepage from original downstream slope part of modifications in progress.

OUTLET WORKS

(Reservoir Drain)

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Not applicable. Reservoir drain conduit is cast iron with PVC extension downstream from gate valve.	
INTAKE STRUCTURE	N/A	
OUTLET STRUCTURE	N/A	
OUTLET CHANNEL	Reservoir drain conduit discharges into downstream channel. Downstream channel modifications are not complete.	
EMERGENCY GATE	N/A	

PRINCIPAL SPILLWAY

VISUAL EXAMINATION OF		OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR		Principal spillway has concrete weir. Concrete in excellent condition. Concrete cap of core wall and concrete weir of principal spillway were reconstructed during November, 1980.	
APPROACH CHANNEL		Not applicable.	
DISCHARGE CHANNEL		Bottom and sidewalls of principal spillway in excellent condition. Original concrete sidewalls were reconstructed during November, 1980. Concrete bottom of spillway was sand blasted and coated with bituminous mastic.	
BRIDGE AND PIERS		None	

AUXILIARY SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	None	
APPROACH CHANNEL	Excavated into soil. Still under construction. Will be seeded in Spring of 1981.	
DISCHARGE CHANNEL	Same as Approach Channel.	
BRIDGE AND PIERS	None	

(EMERGENCY SPILLWAY OR RIGHT CORE WALL)

VISUAL EXAMINATION OF		OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR		Top of concrete core wall will function as a weir. Concrete is in excellent condition - cap recently replaced.	
APPROACH CHANNEL	None		
DISCHARGE CHANNEL		Discharge will occur onto the unvegetated downstream slope of the embankment.	
BRIDGE AND PIERS		Pier adjacent to pump house at emergency spillway section.	

INSTRUMENTATION


<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
MONUMENTATION/SURVEYS	None	
OBSERVATION WELLS	None	
WEIRS	None	
PIEZOMETERS	None	
OTHER	None	

RESERVOIR

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
SLOPES	Slopes are stable and densely covered with trees and brush.	
SEDIMENTATION	Sedimentation not a significant problem. Three small dams are located upstream of the reservoir to collect sediment. Reservoir drained and dredged in 1960.	

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	Downstream channel directly below dam is still under construction. Access road obstructs channel (See Photo No. 6).	
SLOPES	Gentle sloping and lined with trees and brush. Appear stable.	
APPROXIMATE NO. OF HOMES AND POPULATION	There are 4 homes adjacent to and within a 10 feet elevation difference of the stream about 1 mile below the dam at Rt. 228. Further downstream, the stream flows through the town of Mars, where there are about 10 buildings within a 10 feet elevation difference of the stream.	




FIELD SKETCH TREESDALE FARM DAM

ELEV. (FT.)

1140

1110

1080




DAM CRE
1" = 30'

ELEV. (FT.)


1110

1100

1090



SECTION A-A
1" = 10'



DAM CREST PROFILE - LOOKING UPSTREAM

3.5
1

//////

DATE: MARCH 3, 1981		TREESDALE FARM DAM NATIONAL DAM INSPECTION PROGRAM	DAM CREST PROFILE AND SECTION
SCALE: AS SHOWN			
DR: JLM	CK: PAD	ACKENHEIL & ASSOCIATES CONSULTING ENGINEERS PITTSBURGH, PA., CHARLESTON, W. VA. & BALTIMORE, MD.	
DWG. NO. A 12			

APPENDIX B

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
PHASE 1

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
PHASE 1

NAME OF DAM Treesdale Farm Dam

ID # NDI PA 1069

ITEM	REMARKS
AS-BUILT DRAWINGS	Only design drawings are available. Design drawings were provided by the Pennsylvania Dept. of Environmental Resources, Dam Safety Division. (See Plates No. 1 to 9)
REGIONAL VICINITY MAP	See Appendix E, U.S.G.S. 7.5 min. quadrangle map showing dam site location.
CONSTRUCTION HISTORY	Construction of the dam began in 1924 and was completed in August, 1925. Structural modifications began during the summer of 1980 and were not completed at the time of the field inspection.
TYPICAL SECTIONS OF DAM	See Plates No. 1, 2, 4, and 8.
OUTLETS - PLAN DETAILS CONSTRAINTS DISCHARGE RATINGS	See Plate No. 7 See Plates No. 4 and 8 Temporary access road with 12 inch diameter CMP obstructing downstream channel. See discharge rating calculations, Appendix D.
RAINFALL/RESERVOIR RECORDS	Rainfall records maintained by Treesdale Farms.

ITEM	REMARKS
------	---------

DESIGN REPORTS	Report prepared by Ronald E. Kelley Consulting Engineers, Greensburg, Pennsylvania entitled "Reinforcement of Embankment, Concrete Core Wall and Spillway for Earth Dam at Apple Orchards of Treesdale Farms, Inc." and dated March, 1980.
----------------	--

GEOLOGY REPORTS	None
-----------------	------

DESIGN COMPUTATIONS	None except flood routing computations as described below.
HYDROLOGY & HYDRAULICS	Flood routing computations included in report prepared by Kelley Consulting Engineers.
DAM STABILITY	None
SEEPAGE STUDIES	None

MATERIALS INVESTIGATIONS	None
BORING RECORDS	None
LABORATORY	None
FIELD	None

POST-CONSTRUCTION SURVEYS OF DAM	Surveyed during 1979 by Ronald E. Kelley Consulting Engineers for their study. See Plate No. 6.
----------------------------------	---


BORROW SOURCES	Fill for original embankment obtained on-site; exact location of borrow area unknown. Fill recently placed on downstream embankment slope obtained from hillside near left abutment.
----------------	---

ITEM	REMARKS
MONITORING SYSTEMS	None
MODIFICATIONS	Modifications began during the summer of 1980 and were not completed at time of site inspection (Dec. 8, 1980). Modifications include placing fill on downstream embankment slope, installing drain system, constructing auxiliary and emergency spillway and repairing deteriorated concrete.
HIGH POOL RECORDS	Core wall of embankment (El. 1101.5) reportedly never overtopped.
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	Report prepared by Ronald E. Kelley Consulting Engineers, (See "Design Reports")
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None reported
MAINTENANCE OPERATION RECORDS	Inspections performed by State personnel during 1926, 1967, and 1979.

ITEM	REMARKS
SPILLWAY PLAN	See Plate No. 7
SECTIONS	See Plates No. 7 and 8
DETAILS	See Plates No. 7 and 8
OPERATING EQUIPMENT PLANS & DETAILS	Gate valve of reservoir drain only operating feature. (See Plates No. 1, 3, and 7)
SPECIFICATIONS	Specifications for construction of original embankment contained in DER file. Specifications for modifications included in report prepared by Kelley Consulting Engineers (See Plates No. 6 - 9).
MISCELLANEOUS	The elevations shown on Plates No. 6-8 were based on an assumed principal spillway crest elevation of 1105.5. These elevations are 5.5 feet greater than elevations based on mean sea level.

APPENDIX C

PHOTOGRAPHS



PHOTOGRAPH
KEY MAP




2



4



1



3

C-2



5



6



7



8

C3

APPENDIX D
HYDROLOGIC AND HYDRAULIC
ENGINEERING AND
COMPUTER DATA

APPENDIX D
HYDROLOGY AND HYDRAULICS

Methodology: The dam overtopping analysis was accomplished using the system-ized computer program HEC-1 (Dam Safety Version), July, 1978, prepared by the Hydrologic Engineering Center, U.S. Army Corps of Engineers, Davis, California. A brief description of the methodology used in the analysis is presented below.

1. Precipitation: The Probable Maximum Precipitation (PMP) is derived and determined from regional charts prepared from past rainfall records including "Hydrometeorological Report No. 33" prepared by the U.S. Weather Bureau.

The index rainfall is reduced from 10% to 20% depending on watershed size by utilization of what is termed the HOP Brook adjustment factor. Distribution of the total rainfall is made by the computer program using distribution methods developed by the Corps of Engineers.

2. Inflow Hydrograph: The hydrologic analysis used in development of the overtopping potential is based on applying a hypothetical storm to a unit hydrograph to obtain the inflow hydrograph for reservoir routing.

The unit hydrograph is developed using the Snyder method. This method requires calculation of several key parameters. The following list give these parameters, their definition and how they were obtained for these analyses.

<u>Parameter</u>	<u>Definition</u>	<u>Where Obtained</u>
C_t	Coefficient representing variations of watershed	From Corps of Engineers *
L	Length of main stream channel	From U.S.G.S. 7.5 minute topographic map
L_{ca}	Length on main stream to centroid of watershed	From U.S.G.S. 7.5 minute topographic map
C	Peaking coefficient	From Corps of Engineers *
A	Watershed size	From U.S.G.S. 7.5 minute topographic map

3. Routing: Reservoir routing is accomplished by using Modified Puls routing techniques where the flood hydrograph is routed through reservoir storage. Hydraulic capacities of the outlet works, spillways and the crest of the dam are used as outlet controls in the routing.

The hydraulic capacity of the outlet works can either be calculated and input or sufficient dimensions input and the program will calculate an elevation-discharge relationship.

Storage in the pool area is defined by an area-elevation relationship from which the computer calculates storage. Surface areas are either planimetered from available mapping or U.S.G.S. 7.5 minute series topographic maps or taken from reasonably accurate design data.

4. Dam Overtopping: Using given percentages of the PMF the computer program will calculate the percentage of the PMF which can be controlled by the reservoir and spillway without the dam overtopping.

* Developed by the Corps of Engineers on a regional basis for Pennsylvania.

HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: Woodland and apple orchard.

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 1100.0 feet (45 acre-feet)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 1101.8 feet (55 acre-feet)

ELEVATION MAXIMUM DESIGN POOL: 1101.8 feet (existing), 1103.5 feet (design)

ELEVATION TOP D.A.M.: 1101.8 feet (existing), 1103.5 feet (design)

EMERGENCY SPILLWAY

- a. Elevation 1101.5 feet
- b. Type Embankment overflow section (top of core wall will serve as weir crest)
- c. Width 140 feet (existing), 87 feet (design)
- d. Length 3 feet length over core wall
- e. Location Embankment section between principal and auxiliary spillways
- f. Number and Type of Gates None

OUTLET WORKS

- a. Type Principal overflow spillway and auxiliary spillway channel
- b. Location Principal spillway-center of embankment, auxiliary spillway-right abutment
- c. Entrance Invert 1100.0 feet (principal spillway), 1101.1 feet (auxiliary spillway)
- d. Exit Invert 1082 feet (principal spillway), 110.0 feet (auxiliary spillway)
- e. Emergency Drawdown Facilities 10 inch diameter reservoir drain pipe with gate valve.

HYDROMETEOROLOGICAL GAGES

- a. Type Rain gauge
- b. Location Farm office of Treesdale Farms
- c. Records Rainfall records

MAXIMUM NON-DAMAGING DISCHARGE 211 cfs. at El. 1101.8

HEC-1-DAM SAFETY VERSION
HYDROLOGY AND HYDRAULIC ANALYSIS
DATA BASE

NAME OF DAM:	Treesdale Farm Dam
Drainage Area	0.49 sq. mi.
Spillway Design Flood (100 year frequency)	5.0 in./24 hr.
Snyder Unit Hydrograph Parameters	
Zone	27
C _p	0.40
C _t	2.7
L	0.83 miles
L _{ca}	0.30 miles
$t_p = 2.7(L \times L_{ca})^{0.3}$	1.78 hour
Loss Rates	
Initial Loss	0.01 in.
Constant Loss Rate	0.0001 inches/hour
Basic Flow Generation Parameters	
Flow at Start of Storm	1.5 cfs/square mile
Base Flow Cutoff	0.05 Q _p
Recession Ratio	2.0
Principal Spillway Data (Proposed modifications incomplete at time of site reconnaissance)	
Crest Length	15.7 feet
Freeboard	
Existing	1.8 feet
Proposed	3.5 feet
Discharge Coefficient	3.5
Exponent	1.5
Discharge Capacity	
Existing	100 cfs
Proposed	490 cfs
Auxiliary Spillway Data (Proposed modifications incomplete at time of site reconnaissance)	
Crest Length	
Existing	14 feet
Proposed	20 feet
Freeboard	
Existing	1.3 feet
Proposed	3.0 feet
Discharge Coefficient	3.0

Exponent	1.5
Discharge Capacity	
Existing	25 cfs
Proposed	66 cfs
Emergency Spillway Data (Proposed modifications incomplete at time of site reconnaissance)	
Crest Length	
Existing	140 feet
Proposed	87 feet
Freeboard	
Existing	0.3 feet
Proposed	2.0 feet
Discharge Coefficient	3.2
Exponent	1.5
Discharge Capacity	
Existing	90 cfs
Proposed	1110 cfs.

Notes:

1. Rainfall amount for 100 year frequency storm obtained from U.S. Weather Bureau TP 40.
2. Hydrological zone defined by Corps of Engineers, Baltimore District, for determining Snyder's Coefficients (C_p and C).

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79

A1 NON BREACH ANALYSIS OF TREESDALE FARM DAM
 A2 SNYDER METHOD, 100 YEAR FREQ. 24 HOUR STORM, MOD PULS ROUTING
 A3 ADJUST LOSS RATES & RAINFALL TO INCREASE PEAK FLOW TO 497 CFS
 B 150 0 20 0 0 0 0 0 -4 0
 B1 5 0 0 0 0 0 0 0 0
 J 1 9 0 0 0 0 0 0 0
 J1 1.0 2.0 2.2 2.4 2.6 2.7 2.8 2.9 3.0
 K 0 LAKE 0 0 0 0 1 0 0
 K1 COMPUTATION OF INFLOW HYDROGRAPH
 M 0 1 0.49 0 0 0 0 0 1
 O 72 0
 O1 0.002 0.006 0.002 0.002 0.008 0.003 0.002 0.010 0.003 0.006
 O1 0.024 0.008 0.002 0.009 0.003 0.002 0.007 0.002 0.014 0.057
 O1 0.019 0.017 0.068 0.023 0.022 0.085 0.028 0.055 0.216 0.072
 O1 0.020 0.079 0.026 0.016 0.062 0.021 0.062 0.246 0.082 0.075
 O1 0.295 0.098 0.094 0.369 0.123 0.237 0.934 0.311 0.087 0.344
 O1 0.115 0.069 0.270 0.090 0.002 0.006 0.002 0.002 0.008 0.003
 O1 0.002 0.010 0.003 0.006 0.024 0.008 0.002 0.009 0.003 0.002
 O1 0.007 0.002
 T 0 0 0 0 0 0 0 0 0
 W 1.78 0.40 0 0 0 0 0 0 0
 X -1.5 -0.05 2.0 0 0 0 0 0 0
 K 1 DAM 0 0 0 0 1 0 0
 K1 MOD PULS ROUTING OF FLOW THRU TREESDALE FARM DAM
 Y 0 0 0 1 1 0 0 0 0
 Y1 1 0 0 0 0 0 45 -1 0
 Y41100.0 1100.5 1101.0 1101.5 1101.8
 Y5 0 19 60 122 211
 \$\$ 0 8.0 45 55 57 62 70 279 0
 \$E1082.0 1090.0 1100.0 1101.5 1101.8 1102.5 1103.5 1120.0 0
 \$\$1100.0
 \$D1101.8 3.3 1.5 340
 K 99
 A
 A
 A
 A
 A

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT LAKE
 ROUTE HYDROGRAPH TO DAM
 END OF NETWORK

HEC-1 Input Data and Program Sequence

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79

RUN DATE: 18 MAR 81
 RUN TIME: 15. 1.59

NON BREACH ANALYSIS OF TREESDALE FARM DAM
 SNYDER METHOD, 100 YEAR FREQ. 24 HOUR STORM, MOD PULS ROUTING
 ADJUST LOSS RATES & RAINFALL TO INCREASE PEAK FLOW TO 497 CFS

JOB SPECIFICATION
 NQ NHR NMIN IDAY IHR IMIN METRC IPLT IPRT NSTAN
 150 0 20 0 0 0 0 0 -4 0
 JOPER NWT LROPT TRACE
 5 0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 1 NRTIO= 9 LRTIO= 0
 RTIOS= 1.00 2.00 2.20 2.40 2.60 2.70 2.80 2.90 3.00

SUB-AREA RUNOFF COMPUTATION

COMPUTATION OF INFLOW HYDROGRAPH

ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO
 LAKE 0 0 0 0 0 1 0 0

HYDROGRAPH DATA
 IHYDG IUHG TAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL
 0 1 0.49 0.0 0.49 0.0 0.0 0 1 0

LOSS DATA
 LROPT STRKR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP
 0 0.0 0.0 1.00 0.0 0.0 1.00 0.0 0.0 0.0 0.0

UNIT HYDROGRAPH DATA
 TP= 1.78 CP=0.40 NTA= 0

RECESSION DATA
 STRTQ= -1.50 QRCSN= -0.05 RTIOR= 2.00

UNIT HYDROGRAPH 56 END-OF-PERIOD ORDINATES, LAG= 1.77 HOURS, CP= 0.40 VOL= 1.00
 5. 18. 37. 55. 68. 71. 66. 60. 54. 49.
 44. 40. 36. 33. 30. 27. 24. 22. 20. 18.
 16. 15. 13. 12. 11. 10. 9. 8. 7. 7.
 6. 5. 5. 4. 4. 4. 3. 3. 3. 2.
 2. 2. 2. 2. 1. 1. 1. 1. 1. 1.
 1. 1. 1. 1. 1. 0.

HEC-1 Analysis Output

END-OF-PERIOD FLOW
MO.DA HR.MN PERIOD RAIN EXCS LOSS COMP Q MO.DA HR.MN PERIOD RAIN EXCS LOSS COMP Q

SUM 5.00 5.00 0.0 4791.
(127.)(127.)(0.)(135.67)

TOTAL RAIN	5.00,	TOTAL RAINFALL EXCESS	5.00,	TOTAL FLOW	4791.
TOTAL RAIN	10.01,	TOTAL RAINFALL EXCESS	10.01,	TOTAL FLOW	9568.
TOTAL RAIN	11.01,	TOTAL RAINFALL EXCESS	11.01,	TOTAL FLOW	10530.
TOTAL RAIN	12.01,	TOTAL RAINFALL EXCESS	12.01,	TOTAL FLOW	11482.
TOTAL RAIN	13.01,	TOTAL RAINFALL EXCESS	13.01,	TOTAL FLOW	12444.
TOTAL RAIN	13.51,	TOTAL RAINFALL EXCESS	13.51,	TOTAL FLOW	12925.
TOTAL RAIN	14.01,	TOTAL RAINFALL EXCESS	14.01,	TOTAL FLOW	13396.
TOTAL RAIN	14.51,	TOTAL RAINFALL EXCESS	14.51,	TOTAL FLOW	13873.
TOTAL RAIN	15.01,	TOTAL RAINFALL EXCESS	15.01,	TOTAL FLOW	14356.

HYDROGRAPH ROUTING

MOD PULS ROUTING OF FLOW THRU TREESDALE FARM DAM

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
DAM	1	0	0	0	0	1	0	0

ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	LSTR
0.0	0.0	0.0	1	1	0	0	0

NSTPS	NSTD	LAG	AMSKK	X	TSK	STORA	ISPRAT
1	0	0	0.0	0.0	0.0	45.	-1

STAGE	1100.00	1100.50	1101.00	1101.50	1101.80
-------	---------	---------	---------	---------	---------

FLOW	0.0	19.00	60.00	122.00	211.00
------	-----	-------	-------	--------	--------

CAPACITY=	0.	8.	45.	55.	57.	62.	70.	279.
-----------	----	----	-----	-----	-----	-----	-----	------

ELEVATION=	1082.	1090.	1100.	1102.	1102.	1103.	1104.	1120.
------------	-------	-------	-------	-------	-------	-------	-------	-------

CREL	SPWID	COQW	EXPW	ELEVL	COQL	CAREA	EXPL
1100.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA

TOPEL	COQD	EXPD	DAMWID
1101.8	3.3	1.5	340.

PEAK OUTFLOW IS	194.	AT TIME	18.00 HOURS
PEAK OUTFLOW IS	393.	AT TIME	17.67 HOURS
PEAK OUTFLOW IS	433.	AT TIME	17.67 HOURS
PEAK OUTFLOW IS	472.	AT TIME	17.67 HOURS
PEAK OUTFLOW IS	512.	AT TIME	17.67 HOURS
PEAK OUTFLOW IS	531.	AT TIME	17.67 HOURS
PEAK OUTFLOW IS	551.	AT TIME	17.67 HOURS
PEAK OUTFLOW IS	571.	AT TIME	17.67 HOURS
PEAK OUTFLOW IS	590.	AT TIME	17.67 HOURS

HEC-1 Analysis Output

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	RATIOS APPLIED TO PRECIPITATION					
			PLAN	RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5
				1.00	2.00	2.20	2.40	2.60

OPERATION	STATION	AREA	RATIOS APPLIED TO PRECIPITATION			
			RATIO 6	RATIO 7	RATIO 8	RATIO 9
			2.70	2.80	2.90	3.00

HYDROGRAPH AT LAKE	0.49	1	96.	393.	432.	471.	510.	530.	550.	569.	589.
			(1.27)	(5.56)	(11.12)	(12.23)	(13.34)	(14.45)	(15.01)	(15.57)	(16.68)

ROUTED TO DAM	0.49	1	194.	393.	433.	472.	512.	531.	551.	571.	590.
			(1.27)	(5.50)	(11.14)	(12.25)	(13.37)	(14.49)	(15.04)	(15.60)	(16.72)

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1		INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
	ELEVATION	1100.00	1100.00	1101.80
	STORAGE	45.	45.	57.
	OUTFLOW	0.	0.	211.

RATIO OF SDF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
1.00	1101.74	0.0	57.	194.	0.0	18.00	0.0
2.00	1102.02	0.22	59.	393.	5.00	17.67	0.0
2.20	1102.06	0.26	59.	433.	5.67	17.67	0.0
2.40	1102.09	0.29	59.	472.	6.33	17.67	0.0
2.60	1102.12	0.32	59.	512.	6.67	17.67	0.0
2.70	1102.14	0.34	59.	531.	7.33	17.67	0.0
2.80	1102.15	0.35	60.	551.	7.33	17.67	0.0
2.90	1102.17	0.37	60.	571.	7.33	17.67	0.0
3.00	1102.18	0.38	60.	590.	8.00	17.67	0.0


BY: PAD
 DATE: 1/26/81
 CHECKED: MLM
 DATE: 1/29/81

ACKENHEIL & ASSOCIATES
 CONSULTING ENGINEERS
 BALTIMORE, MARYLAND

PROJECT NO. 80074

SUBJECT: Compute Rating Curve for Spillways
 Treesdale Farm Dam

SHEET NO. D-10 OF



1. Find discharge of Principal Spillway to El. 1101.5


$$Q = CLH^{1.5}$$

$L = 15.7'$
 sharp-crested weir $C = 3.22 + .44 H/P$

$$L + P = 5 \text{ ft.}$$

Reservoir Elev.	H	C	Q (cfs)
1100.0	0	—	0
1100.5	.5	3.26	18
1101.0	1.0	3.31	52
1101.5	1.5	3.35	97

2. Find discharge of Auxiliary Spillway to El. 1101.5



$$Q = CLH^{3/2}$$

let $C = 3.0$
 use Avg. H.

Reservoir Elevation	H	Avg. H	L	Q cfs.
1100.0	0	—	—	0
1100.5	.4	.12	4	1
1101.0	.9	.45	9	8
1101.5	1.4	.7	14	25

Combined for Both Spillways.

El. 1100.0	Q = 0
1100.5	= 19 cfs
1101.0	= 60 cfs
1101.5	= 122 cfs

PAD

1/26/81

MLM

1/29/81

PROJECT NO 80074

Compute Rating Curve for Spillways
Treesdale Farm dam.

SHEET NO D-11 OF

3. Find discharge over right core wall

For L → use length of Wall + spillways

$$L = 140 + 15.7 + 14 \approx 170 \text{ ft.}$$

$$H = \text{El. } 1101.8 - 1101.5 = 0.3 \text{ ft.}$$

Consider core wall to act as sharp crested weir

$$\text{Let } C = 3.22 + .44 H^{1/4} \\ C = 3.2$$

$$H = .3' \quad P = 5'$$

$$\text{@ El. } 1101.8 \quad Q = (3.2 \times 170 \times 0.3^{1.5}) + 122 = 89 + 122 = 211 \text{ cfs.}$$

4 Find discharge if entire dam is overtopped

Assume that fill downstream of curved core wall section will be eroded and that top of core wall for this section will act as sharp crested weir.

$$Q = CLH^{3/2} + 211 \text{ cfs.}$$


$$C = 3.22 + .44 H^{1/4} \\ \text{use } P = 5'$$

Reservoir El.	H	L	C	Q (cfs)
1101.8	—	—	—	211
1102.0	0.2	365'	3.2	315
1102.5	0.7	↓	3.3	916
1103.0	1.2	↓	3.3	1794
1103.5	1.7	↓	3.4	2962
1104.0	2.2	↓	3.4	4260

5 Find Discharge of Principal + Emergency Spillway @ El. 1101.5 if Auxiliary Spillway is completed according to Plan.

Discharge of Principal Spillway @ El. 1101.5 = 97 cfs.

Auxiliary Spillway



$$Q = CLH^{3/2}$$

$$\text{let } C = 3.0$$

$$\text{let } L = \text{avg length} = 22 \text{ ft.}$$

$$\text{let } H = 1.0 \text{ ft.}$$

$$Q = 3.0 \times 22 \times 1.0^{3/2} = 66 \text{ cfs.}$$


$$\text{Total} = 97 + 66 = 163 \text{ cfs.}$$

Compute Rating Curve for Spillways
Treedale Farm Dam.

SHEET NO. D-12 OF

Compute spillway discharge at crest of planned
Embankment, El. 1103.5.

Principal Spillway Cross-Section



$$Q = CLH^{3/2}$$

$$H = 3.5 \text{ ft.}$$

$$\text{Use } C = 3.3$$


$$\text{Avg. } L = (15.7 + 29.7) / 2 = 22.7'$$

$$Q = 3.3 \times 22.7 \times 3.5^{3/2} = 490 \text{ cfs}$$

Auxiliary Spillway

$$\text{At El. 1101.5 } Q = 66 \text{ cfs.}$$

Emergency Spillway. (Include Auxiliary Spillway above El. 1101.5.)



Not to scale

$$Q = CLH^{3/2}$$

$$\text{Use } C = 3.3$$

$$\text{Use } L = 119 \text{ ft.}$$

$$H = 2.0 \text{ ft.}$$

$$L = 87 + 20 + 12/2 - 25 = 88'$$

$$Q = 3.3 \times 119 \times 2^{3/2} = 1110 \text{ cfs}$$

$$\text{Total } Q = 490 + 66 + 1110 = 1466 \text{ cfs}$$

PAD
1/13/81
TED
FEB 19, 1981

UNITED STATES

PROJECT NO. 80074

Treesdale Farm Dam.

Reservoir Storage Volume vs. Elevation. SHEET NO. D-13 OF

1. Reservoir surface area for different elevations were planimetered from Plate # 5, showing topography of reservoir area and dated March 30, 1925. Also used USGS topo map for area at El. 1120. Storage volume was calculated by average end area method.

2. Area.

Plate #5 scale: 1 in. = 97.7 ft. (of reduction)

El. 1082.	Area = $0.50 \text{ in}^2 \times 97.7^2 \div 43560 =$	0.11 acres
1082.5	Area = 2.35 in^2	= 0.51
1090	Area = 7.2 in^2	= 1.58
1095	Area = 17.0 in^2	= 3.72
1100	Area = 27.1 in^2	= 5.94

El. 1120 obtained from USGS Topo. scale: 1" = 2000'

1120 Area = $0.19 \text{ in}^2 \times 2000^2 \div 43560 =$ 17.45 acres

Top of emergency spillway El. = 1101.5 Area = $(17.45 - 5.94) \times \frac{11.5}{20} + 5.94 =$ 6.80
Top of core wall El. = 1101.8 Area = $(17.45 - 5.94) \times \frac{18}{20} + 5.94 =$ 6.97
Future top of dam = 1103.5 Area = $(17.45 - 5.94) \times \frac{3.5}{20} + 5.94 =$ 7.95

3. Storage Volume.

El. 1082 - 1082.5	Vol. = $(.11 + .51) / 2 \times .5 =$.16 AF
1082.5 - 1090	Vol. = $(.51 + 1.58) / 2 \times 7.5 =$	7.84
1090 - 1095	Vol. = $(1.58 + 3.72) / 2 \times 5 =$	13.25
1095 - 1100	Vol. = $(3.72 + 5.94) / 2 \times 5 =$	24.15
1100 - 1101.5	Vol. = $(5.94 + 6.80) / 2 \times 1.5 =$	9.56
1101.5 - 1101.8	Vol. = $(6.80 + 6.97) / 2 \times 0.3 =$	2.07
1101.8 - 1103.5	Vol. = $(6.97 + 7.95) / 2 \times 1.7 =$	12.68

4. Σ Volume.

El. 1082	Vol. = 0
1082.5	.16 AF
1090	8.00 AF
1095	21.25 AF
1100	45.40 AF
1101.5	54.96 AF
1101.8	57.03 AF
1103.5	69.71 AF

BY: PAD
DATE: 3/7/81
PROJECT:
DRAWN:

ALFRED E. STANTZ ASSOCIATES
INCORPORATED
1000 W. 10th St.
Des Moines, IA 50319

PROJECT NO. 740074

PROJECT: Treedale Farm Dam - hydrology

SHEET: D-14

Calculate Peak Inflow for 100 year storm

Ohio River Basin, Regression equation for peak flow
(obtained from Baltimore Dist. Corps of Engineers)

$$Q_{100} = 120.38 (D.A. \times S^{1/2})^{0.744089}$$

where

$$D.A. = \text{drainage area} = 0.49 \text{ mi.}^2$$

$$S = \text{slope of longest watercourse in ft./mi.}$$

$$S = \frac{1260 - 1100}{4500 / 5280} = \frac{160 \text{ ft.}}{.852 \text{ mi.}} = 188 \text{ ft./mi.}$$

$$Q_{100} = 120.38 (.49 \times 188^{1/2})^{0.744} = 497 \text{ cfs.}$$

BY PAD
DATE 3/18/81
CHECKED
DATE

ACKENHEIL & ASSOCIATES
CONSULTING ENGINEERS
BALTIMORE, MARYLAND

PROJECT NO. 80074

SUBJECT: Treesdale Farm Dam Hydrology

SHEET NO. D-15 OF

Rainfall distribution for 100 year frequency - 24 hour storm

TP-40 Rainfall

6 hr. - 3.9 in.
12 hr. - 4.8 in.
24 hr. - 5.0 in.

Divide into 4 - 6 hr. intervals
use 18 hr. rainfall of 4.9 in.

Obtain Rainfall Amounts for 20 min. time intervals.

Duration	Rainfall	% of 24 hr.	Inc. Rainfall	Rank
6	3.9	78 %	3.9	1
12	4.8	96 %	0.9	2
18	4.9	98 %	0.1	3
24	5.0	100 %	0.1	4

Use 4, 2, 1, 3 Rank

* Use NOAA Hydro 35 distribution for 20 min. time intervals (16, 63, 21)

Time	Inc. Rainfall	EM 1110-2-1411 Distribution	Rainfall / Inc.	20 min. int. Rainfall / Inc.		
				20	40	60
1	0.1	10%	0.010	.0016	.0063	.0021
2		12	0.012	.0019	.0076	.0025
3		15	0.015	.0024	.0095	.0032
4		38	0.038	.0061	.0239	.0080
5		14	0.014	.0022	.0088	.0029
6		11	0.011	.0018	.0069	.0023
7	0.9	10	0.090	.0144	.0567	.0189
8		12	0.108	.0173	.0680	.0227
9		15	0.135	.0216	.0851	.0284
10		38	0.342	.0547	.2155	.0718
11		14	0.126	.0202	.0794	.0265
12		11	0.099	.0158	.0624	.0208
13	3.9	10	0.390	.0624	.2457	.0819
14		12	0.468	.0749	.2948	.0983
15		15	0.585	.0936	.3686	.1229
16		38	1.482	.2371	.9337	.3112
17		14	0.546	.0874	.3440	.1147
18		11	0.429	.0686	.2703	.0901
19	0.1	10	0.010	.0016	.0063	.0021
20		12	0.012	.0019	.0076	.0025
21		15	0.015	.0024	.0095	.0032
22		38	0.038	.0061	.0239	.0080
23		14	0.014	.0022	.0088	.0029
24		11	0.011	.0018	.0069	.0023

APPENDIX E
LOCATION PLAN AND PLATES


LIST OF PLATES

- Page E-1 Location Plan
- Plate No. 1 Treesdale Farm Dam, Cross Section,
(design drawing of original embankment
dated 1925).
- Plate No. 2 Treesdale Farm Dam, Longitudinal Sectional,
(design drawing of original embankment
dated 1925)
- Plate No. 3 Treesdale Farm Reservoir, General Plan,
(design drawing of original embankment
dated 1925)
- Plate No. 4 Treesdale Farm Dam, Detail Plans of Main
and Auxiliary Spillway, (design drawing
of original embankment dated 1925)
- Plate No. 5 Treesdale Farm, Proposed Private Reservoir,
(design drawing of original embankment
dated 1925)
- Plate No. 6 Ronald E. Kelley Consulting Engineers,
Existing Topography and Conditions of
Embankment, Spillway, and Facilities
- Plate No. 7 Ronald E. Kelley Consulting Engineers,
Proposed Embankment Reinforcement and
Details
- Plate No. 8 Ronald E. Kelley Consulting Engineers,
Sections through Embankment and Spillway
- Plate No. 9 Ronald E. Kelley Consulting Engineers,
Proposed Embankment Reinforcement and
Details (shows subsurface drain design
and construction notes not included on
Plate No. 7)

MARS U.S.G.S. 1 1/2 MIN. QUAD.

PENNSYLVANIA

QUADRANGLE LOCATION



DATE: MARCH 3, 1981

SCALE: 1" = 2000'


DR: JLM CK: PAD

DWG. NO. E 1

TREESDALE FARM DAM
NATIONAL DAM INSPECTION PROGRAM

ACKENHEIL & ASSOCIATES
CONSULTING ENGINEERS
PITTSBURGH, PA., CHARLESTON, W. VA. & BALTIMORE, MD.

LOCATION PLAN



CROSS SECTION

A B
SHOWING





PROPOSED

TREESDALE FARM DAM

J.C. TREES, ESQ.

SCALE 1" = 10'

MARCH 30 1925.



CROSS SECTIONS
SHOWING
REINFORCEMENT
SCALE 1"=3 Ft.





PLATE NO. I



LONGITUDINAL

PROPOSED

TREESDALE FA


J.C. TREES,

SCALE

HORIZONTAL

VERTICAL

MARCH 30, 1911



NAL SECTION

PROPOSED

E FARM DAM

DEES, ESQ.


SCALE


HORIZONTAL 1" = 50 Ft.

VERTICAL 1" = 20 Ft.

JAN 30, 1925.

PLATE NO. 2







GENERAL PLAN
TREESDALE FARM RESERVOIR
J.C. TREES, ESQ.

SCALE 1" = 20' MARCH 30, 1925


PLATE NO. 3




ELEVATION



MAIN SPILLWAY



ELEVATION



AUXILIARY SPILLWAY

DETAIL

MAIN & AUXILIARY

SECTION



ELEVATION, - SECTION

TREESDALE

J.C. TREESDALE

SCALE 1 INCH = 5 FEET


CROSS SECTION
SHOWING
2 INCH W I PIPE REINFORCEMENT




SS SECTION

AIL PLANS
OF
ILIARY SPILLWAY
SHOWING
TION & REINFORCEMENT
LE FARM DAM
REES, ESQ.
5 FT. MARCH 30 1925.

PLATE NO. 4




PROPOSED
PRIVATE RESERVOIR
ON
TREESDALE FARM
JC TREES, ESQ
SCALE 1"=50' MARCH 30, 1901



SED
SERVOR
FARM
ESU
M...

PLATE NO. 5






PLAN - EXISTING DAM AND SPILLWAY AREA
SCALE: 1"=20'

NOTI

REVISIONS	DATE	BY	DESCRIPTION

MOVED)



NOTE: ELEVATIONS SHOWN ARE 5.5' GREATER THAN ELEVATIONS BASED ON MEAN SEA LEVEL.


PLATE NO. 6

SHEET 1 OF 3



	RONALD E. KELLEY CONSULTING ENGINEERS GREENSBORO, NORTH CAROLINA 27409		EXISTING TOPOGRAPHY AND CONDITIONS EMBANKMENT, SPILLWAY, AND FACILITIES	
	TREESDALE FARMS, INC. APPLE ORCHARDS MARS, PENNSYLVANIA 16046		DRAWN BY: <i>W.E.H.</i> 1-5-80	CHECKED BY: <i>H.K.</i> 3-20-80
			APPROVED BY: <i>W.E.H.</i> 1-2-80	79-



ATION






1 OF 3	
AND CONDITIONS OF DAY, AND FACILITIES	
80	79-113-E1
80	
80	



EARTH EMPLACEMENT CLOSURE
SECTION E-E
SCALE 1"=50'

NOTE: ELEVATIONS SHOWN ARE 5.5' GREATER THAN
ELEVATIONS BASED ON MEAN SEA LEVEL.



- REINFORCEMENT AND REPAIR OF CONCRETE AND EARTH DAM WITH SPILLWAY**
- Place drill pipes and grout area bould dam (upstream behind cracks) in concrete core-wall as shown in Detail "A".
 - Use grout mix of one part Portland Cement with one part water.
 - Pressure-grout each boring from the bottom upward, beginning at toe of work (or 3 maximum depth of drill hole, whichever occurs first).
 - Grout drill hole in 5-foot sections to refusal, using a maximum pressure of 1 psi per foot of height, measured from toe ground surface to the top of the section being grouted.
 - Place additional borings for grouting, if necessary and as directed by the Engineer and pump grout to achieve a more complete seal of the seepage.
 - Repair the existing concrete Cap on top of the concrete Core-wall.
 - Chip the spalled and deteriorated concrete down to sound, hard concrete using pneumatic tools or hand blasting equipment, if necessary. Patch surface thoroughly with old water. Cracks and voids should be vacuumed or blown clear by use of oil-free, clean air.
 - Clean all exposed steel to remove all rust, scale, dirt and other loose or foreign material. Steel may be cleaned using sandblasting, or such proprietary rust removal as the acid type in military spec. MIL-H-10078 or by application of caustic solvent and wire brushing.
 - Apply "Cobra Bonding Compound", as manufactured by the Sika Chemical Corp., or equal, to bond the existing hard concrete to the subsequent "fresh-troweled" concrete patching. (All work to be conducted in strict compliance with the Manufacturer's directions and instructions.) Apply Sika adhesive to metal as soon as possible after cleaning to prevent surface from reoxidizing.
 - Apply "Sika Dur Lo-Med Gel" mortar, mixed with "Sika Quarzite Aggregate" as manufactured by Sika Chemical Corporation, or equal, in a ratio of 1 part mortar 3 parts of Quarzite Aggregate (which is a specially graded and oven-dried aggregate) or equal, to fill concrete areas properly prepared to receive patching. This concrete material is to be mixed in a stiff mix and trowled in place to fit, restore the original Cap geometry.
 - Seal the repaired concrete Cap with "Sikagard W-84" epoxy coating, limestone B in color. (Sandblast entire surface before application.) Extend the coating downstream, vertical face of the Core Wall to the top of water.
 - Repair and restore the concrete training walls along the existing Spillway, using materials and techniques described and required in Note 2.
 - Relocate the outdoor Privy along the right downstream abutment, as shown.
 - Place a compacted earth fill in front of the existing Embankment.
 - Cover the downstream slope of the existing embankment with a crushed stone or draining blanket; the earth fill is compacted from the bottom. (Provide 6 drains along the toe as shown.)
 - Place well in lifts out to exceed 8 inches and compact to 90 percent of Proctor. (95 percent adjacent the spillway and beneath the rip rap slopes.)
 - Provide rip rap slopes adjacent the Spillway Training Walls to protect against erosion.
 - Clear the downstream channel of debris and trees. Form a settling basin with rip rap placed at the bottom of the Spillway.

Notes Continued on Drawing No. 79-113-E3

SHEET 2

K	RONALD E. KELLEY		PROPOSED EMBANKMENT REINFO AND DETAILS	
	CONSULTING ENGINEER			
	TRESDALE FARMS, INC.			
	APPLE ORCHARDS		DATE: 11-2-80	79-
	MARS, PENNSYLVANIA 16046		BY: REK	80

PLATE NO. 7

PREPARED
BY AGA
CONCRETE
NOTE 1)

DOWNSTREAM
SLOPE

Hydro core-mill

rock (or 30 feet

ure of 1 psi per
tion being created.

by the Engineer,

Use using pneumatic
ally with clean
oil-free, compressed

on or foreign
by rust removers
sodic solution

Application, use
poured concrete
Manufacturer's
and possible

gate" as
port mortar to
dried
in patching.
use to fit and

limestone gray
meeting d.a.

any, using the same

and stone or slag
(Provide 6" dia. PVC

set of Modified
by slopes.)




ment against erosion

Reinforce with large

KEY 2 OF 3

REINFORCEMENT
IS


79-113-62




NOTE: ELEVATIONS SHOWN ARE 5.5' GREATER THAN ELEVATIONS BASED ON MEAN SEA LEVEL.

REFERENCE DRAWING	REVISION	DESCRIPTION


WITH SEED & MULCH
TREATMENT - SEE NOTE



WY RIP RAP SIDE SLOPES,
ADJACENT RAILWAY SIDES






WASHED STONE (TO BE CONSTRUCTED
IF ENCOUNTERED)



ELEVATION
1110
1105
1100
1095
1090
1085

ELEVATION
1110
1105
1100
1095
1090
1085

ELEVATION
1110
1105
1100
1095
1090



REINFORCEMENT AND REPAIR OF CONCRETE AND EARTH DAM WITH SPILLWAY (Cont'd)

6. Provide a closure section using rock gabions placed along the eastern end of the earth embankment to protect the pump house. Gabions to be PVC coated.
 - (a) Return PVC coated rock gabions at the extreme eastern end of the concrete cap to form the northwestern wall of the auxiliary spillway channel.
 - (b) Grouting of the gabions with a lean mortar mix (1 part cement to 1 part sand) is desirable but not necessary.
7. Plan, grade, seed and mulch the exposed slopes of the new embankment, auxiliary spillway channel and all other surface areas of soil disturbed by the construction activities.


SHEET 3

HAN

PLATE NO. 8

	RONALD E. KELLEY		SECTIONS THROUGH EMBANKMENT & SPILLWAY	
	CONSULTING ENGINEERS		DESIGNED BY	WFA 12-00
	TREESDALE FARMS, INC.		CHECKED BY	EDJ 13-00
	MARS, PENNSYLVANIA 16046		APPROVED BY	DEK 14-00

79-11



SHEET 3 OF 3

WILLIAM
WILLY

79-113-E3


REMARKS:

1. AREA SHOWN TO BE EXCAVATED AT LEAST 1' OR UNTIL FIRM SOILS ARE ENCOUNTERED TO PREPARE FOR FILL REPAIRS.

AREA REQUIRED TO BE EXCAVATED AND REMOVED BY ORIGINAL PLANS

AREA OF ADDITIONAL SOFT MATERIAL REQUIRED TO BE EXCAVATED AND REMOVED

2. THE DESCRIPTION OF CRACKS IN CONCRETE TYPE WALL AND RECOMMENDATIONS FOR SEALING, SEE CHARTS I, II, AND III.



APPENDIX F
REGIONAL GEOLOGY

TREESDALE FARM DAM
NDI ID. NO. PA 1069
REGIONAL GEOLOGY

REGIONAL GEOLOGY

The dam is located in Butler County, approximately one mile south of Mars and immediately north of the Allegheny County-Butler County boundary line. Physiographically, the dam is located in the Kanawha section of the Allegheny Plateau Physiographic Province. The local structure of the plateau in the vicinity of the dam is a broad, shallow spoon shaped trough, trending approximately S30°W. A number of secondary subparallel folds are superimposed on the trough.

The dam is located approximately one mile east of the Mount Nebo Syncline axis which plunges at approximately 4 degrees to the south. The dam overlies the lower to middle portion of the Conemaugh Formation. These rocks are of Pennsylvanian Age and consist of interbedded and discontinuous members of shale, sandstone, limestone, and coal.


SITE GEOLOGY

No subsurface investigation was performed at the dam site. Records indicate that the dam overlies about a 10 to 20 feet layer of clay which overlies shale bedrock.

References

Engineering Characteristics of the Rock of Pennsylvania, McGlade, Geyer and Wilshusen, Pennsylvania Geological Survey, 1972.

Ground Water in Southwestern Pennsylvania, Arthur M. Piper, Pennsylvania Geological Survey, 1933.



MARS QUADRANGLE, BUTLER COUNTY, PENNSYLVANIA

SCALE: 0  1/2 MILE 1:24 000

CONTOUR INTERVAL 20FT. DATUM IS MEAN
SEA LEVEL



DATA OBTAINED FROM PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL RESOURCES TOPOGRAPHIC
AND GEOLOGIC SURVEY 1960

DATE: MARCH 3, 1981		TREESDALE FARM DAM NATIONAL DAM INSPECTION PROGRAM	GEOLOGIC MAP
SCALE: 1"= 2000'			
DR: JLM	CK: PAD	ACKENHEIL & ASSOCIATES CONSULTING ENGINEERS PITTSBURGH, PA., CHARLESTON, W. VA. & BALTIMORE, MD.	
DWG. NO. F 2			

AGE	PERIOD	SYSTEM	COLUMNAR SECTION	PROMINENT BEDS
QUATERNARY				PLEISTOCENE GLACIAL OUTWASH, RIVER TERRACE DEPOSITS AND ALLUVIUM
PERMIAN	DURAND (Pp)	ARTESIAN		UPPER WASHINGTON LIMESTONE
				WASHINGTON COAL
PENNSYLVANIAN	MORRISVILLE (Pp)	ARTESIAN		WYTHEBURG SANDSTONE
				WYTHEBURG COAL
				LANCASTER SANDSTONE
				LANCASTER COAL
	CONEMAUGH (Pp)	ARTESIAN		BENWOOD LIMESTONE
				BRIDGLEY COAL
				PITTSBURGH SANDSTONE
				PITTSBURGH COAL
	CASSIDIAN (Pp)	ARTESIAN		CORNELLEVILLE SANDSTONE
				MORGANTOWN SANDSTONE
				AMES LIMESTONE
				PITTSBURGH RED BEDS
	ALEXANDRIA (Pp)	ARTESIAN		SALTZBURG SANDSTONE
				MAHONING SANDSTONE
MISSISSIPPIAN	POTTSVILLE (Pp)	ARTESIAN		UPPER FREEPORT COAL
				UPPER KITTANNING COAL
				WORTHINGTON SANDSTONE
				LOWER KITTANNING COAL
	POCONO (Pp)	ARTESIAN		HOMEROCK SANDSTONE
				HERCER SANDSTONE, SHALE & COAL
				CORROQUESSING SANDSTONE
				BURBOON SANDSTONE
	POCONO (Pp)	ARTESIAN		CUYAHOGA SHALE
				BEREA SANDSTONE

DATE: MARCH 3, 1981

SCALE: None

DR: AP CK: JEB

F3

TREESDALE FARM DAM
NATIONAL DAM INSPECTION PROGRAM

ACKENHEIL & ASSOCIATES CONSULTING ENGINEERS

GEO SYSTEMS, INC.

1000 BANKSVILLE RD./PITTSBURGH, PA 15216

GEOLOGIC
COLUMN